

SECTION 02111

REMOVAL OF STRUCTURES AND OBSTRUCTIONS

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Includes but not limited to the removal, salvage (give to the government) of usable components including the wheel gate, and wheel. The inlet structure, and principle spillway pipe along with nonsalvagable materials to be disposed of off the forest at a proper disposal site.

1.2 MEASUREMENT

- A. Method: Measure removal of structures and obstructions by the lump sum.

1.3 PAYMENT

- A. The accepted quantity, measured as provided above, will be paid at the contract price per unit of measurement for the pay item listed below that is designated in the SCHEDULE OF ITMES.

- B. Payment will be made under:

Pay Item

Pay Unit

02111 (01) Removal of Structures and Obstructions.....Lump Sum

PART 2 - PRODUCTS

NOT APPLICABLE

PART 3 - EXECUTION

3.1 GENERAL

- A. Topsoil stripping and storage, if required, shall comply with the applicable specification.
- B. The corrugated metal ring and lid will be removed and disposed of as well as the gate stem and inlet structure. The afore mentioned items will be disposed of off site and off forest at a permitted disposal site. The wheel and screw mechanism shall be salvaged and given to the government for reuse. The void where the wheel control is shall be filled with soil and compacted in lifts not to exceed 9 inches of non-compacted material. The fill material shall have sufficient moisture to compact, dry material shall be deemed unacceptable for backfill material.
- C. Backfill for removed items may be excess material from other excavation or borrow from an approved source.

- 1. Backfill material will be free of rocks over 3 inches in diameter.

- D. Not Used
- E. Not Used
- F. Excessive settlement or other evidence of improper backfill shall be corrected by reopening the excavation to the depth required for proper refilling and compaction.

3.2 DISPOSAL

- A. Disposal of debris shall comply with Section 02230 – Site Clearing.

3.3 SEEDING

- A. Seeding, if required, shall comply with Section 02801 - Seeding.

END OF SECTION